

AGREEMENT FOR INTERIOR WORK EXECUTION

Agreement for Interior Work Execution of Residential Flat in Flat no-4024, 2nd floor, DDA, HIG Flat, Jasola, New Delhi.

Space Area – 1700 Sq.Ft. approx.

THIS AGREEMENT IS MADE on 17th May, 2026 Between:

Mr. Noor S/o. Mr. Sarfaraz

R/o. Flat no-4024, 2nd floor, DDA, HIG Flat, Jasola

Hereinafter called the OWNER, the term shall include his assigns and successors.

AND

M/S Arya Enterprises (Proprietor Mr. Prabhat Arya)

Reg. office: D-97B, Sector 15 Noida, U.P.

Head Office: F- 52, 1st Floor, Near Gurudwara, Madhu Vihar, IP Extn. New Delhi – 110092.

Hereinafter called the CONTRACTOR, the term shall include its assigns and successors.

Wherein the owner possesses a residential flat at Residential Flat no-4024, 2nd floor, DDA, HIG Flat, Jasola as per the approved architect's plan, drawings and the specifications, rates and quantities, enclosed or forming part of this agreement.

NOW THIS AGREEMENT IS AS FOLLOWS:

- 1.The Building Contractor shall consider the money to be paid in the manner set forth below to execute and complete the works as per the plan and specifications written below to the satisfaction of the owner.
- 2.This contract is at the per Item rate as mentioned in the detailed estimate. The cost of the contract is Rs. 30,50,176.79/-

**After Cash Discount of 50,000/- The Final Cost shall be Rs. 30,00,176.79/-
(Rupees Thirty Lakhs One Hundred Seventy Seven Only).**

Area & Rate Schedule:

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
Interior Work						
Second Floor						
1	Demolition Area					
1.1	All Over Area					
1.1.1	DEMOLITION WORK	Nos	1.00	1,00,000.00	1,00,000.00	
	Demolition of toilets, Kitchen, wardrobe, Balcony, wonodws, sanitary fixtures, electrical conduting, plaster, existing flooring etc as per discussion,					
	Removing of Debris from Site.					
1.1.2	PCC 1" Thick	0	1.00	40,000.00		it can be avoided
2	Electrical Work					
2.1.1	ELECTRICAL WIRE, SWITCHES & SOCKETS P&F of Wiring for Concealed lights in false ceiling and Extra points as per design. Applying Earthing - 0.75mm, Inverter wiring - 1mm, 6A- 1.5mm, 16A- 2.5mm, AC/ Gyser - 4mm wire (Make: Polycab or equivalent), as & where required. Applying 10 mm wire for main DB to Meter. Supply and fixing of Modular Switch & Sockets (Make: Havells Adiva) MCB (Make: Havells/ Legrand) Labour for fixing Lights & Fans or other electrical items included unless mentioned. AC Copper wire & Drain is excluded Cat 6 wire for internet is excluded	0	1,430.00	185.00	2,64,550.00	Any kind of light fixtures, decorative light, fan, exhaust, chimney, geyser, Profile & cove light fridge etc. are not included

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
--------	-------------	------	------	------	--------	---------

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
3	False Ceiling Work					
3.1	Entrance/Foyer					
3.1.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	0	65.54	132.00	8,651.28	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.2	Drawing Room					
3.2.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	Sq.Ft.	202.00	132.00	26,664.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.3	Dining Room					
3.3.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	Sq.Ft.	175.00	132.00	23,100.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.4	Bathroom 1					
3.4.1	BISON PANEL CEILING Providing & Fixing Biason Panel Ceiling (Make: Everest), fixing with GI Channel, Parameters, sections & Compound taping and finishing.	Sq.Ft.	65.00	132.00	8,580.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
3.5	Bedroom 1					
3.5.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	Sq.Ft.	165.00	132.00	21,780.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.6	Bathroom 2					
3.6.1	BISON PANEL CEILING Providing & Fixing Biason Panel Ceiling (Make: Everest), fixing with GI Channel, Parameters, sections & Compound taping and finishing.	Sq.Ft.	40.00	132.00	5,280.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.7	Master Bedroom					

3.7.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	Sq.Ft.	165.00	132.00	21,780.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
3.8	Master Bathroom					
3.8.1	BISON PANEL CEILING Providing & Fixing Biason Panel Ceiling (Make: Everest), fixing with GI Channel, Parameters, sections & Compound taping and finishing.	Sq.Ft.	40.00	132.00	5,280.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
3.9	Kitchen					
3.9.1	POP FALSE CEILING Providing & Fixing POP False Ceiling, fixing with GI Channel, Parameters, sections & fastners finish in 18-20MM.	Sq.Ft.	83.00	132.00	10,956.00	Cove or strip below 01 feet shall be measured in Ru. Ft.1" Thk. Moulding or Grooves shall be payable at Rs. 50 and Rs. 25 respectively in Ru.Ft.Can be added if required
4	Flooring Work					
4.1	Entrance/Foyer					
4.1.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	72.00	140.00	10,080.00	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required
4.2	Drawing Room					
4.2.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	265.00	140.00	37,100.00	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
4.3	Dining Room					
4.3.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	204.50	140.00	28,630.00	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required
4.4	Bedroom 1					
4.4.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	204.50	140.00	28,630.00	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required
4.5	Bathroom 1					
4.5.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 600x600mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	78.00	140.00	10,920.00	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
4.3	Dining Room					
4.6	Bedroom 2					
4.6.1	TILE FLOORING Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting). In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).	Sq.Ft.	223.67	140.00	31,313.80	As per market Standards, skirting shall be measured in Ru.Ft. as per the mentioned rate. Can be added if required
4.7	Bathroom 2					
4.7.1	TILE FLOORING	Sq.Ft.	47.63	140.00	6,668.20	

	Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 600x600mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting).					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					
4.8	Master Bedroom					
4.8.1	TILE FLOORING	Sq.Ft.	204.50	140.00	28,630.00	
	Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting).					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					
4.9	Master Bathroom					
4.9.1	TILE FLOORING	Sq.Ft.	31.00	140.00	4,340.00	

	Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 600x600mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting).					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					
4.10	Kitchen					
4.10.1	TILE FLOORING	Sq.Ft.	103.00	140.00	14,420.00	
	Providing & Fixing Vitrified Tiles (Up to Rs. 45/- Sq. Ft.) 1600x800mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with mortar (Including normal Grouting).					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
4.11	Bathroom 1					

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
4.11.1	WALL TILE DADO	Sq.Ft.	200.00	135.00	27,000.00	
	Providing & Fixing Vitrified Tiles (Up to Rs. 40/- Sq. Ft.) 1200x600mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with Tile Chemical (Make: Kajaria/ Ultratech or equivalent) Including normal Grouting.					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					
4.12	Bathroom 2					
4.12.1	WALL TILE DADO	Sq.Ft.	206.00	135.00	27,810.00	
	Providing & Fixing Vitrified Tiles (Up to Rs. 40/- Sq. Ft.) 1200x600mm (Make: Kajaria, Somany, Nitco or equivalent) fixing Jointless with Tile Chemical (Make: Kajaria/ Ultratech or equivalent) Including normal Grouting.					
	In case of requirement for 3mm Groove and additional Epoxy Grouting with matching colour shall be payable at Rs. 35/- Sq.ft for (Make: Roff) and Rs. 30/- Sq.ft. for (Make: Lategate, Asian or equivalent).					
5	Plumbing Work					
5.1	Bathroom 1					

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
5.1.1	CP FITTING Provide & fixing 1. Connection Pipe, 2. Spout(Up to Rs. 3500/-) 3. Jaali for Drain (Make: 4"x4"up To Rs. 900pc, drain jali 18"x3" upto 3000/pc) as per requirement, 4. Angle valves (Up to Rs. 1200/-) 5. Cistern flush tank (upto Rs. 4700/-) 6. Extension Nipples, Connection Pipe (Up to 600/-), 7. WC (Up to Rs. 12,500/-), 8. Wash Basin (up to Rs, 12,000/-), 9. Shower head 9"x9" & Shower Rod (up to Rs. 8,000/-) 11.Flush button (upto Rs. 2,000/-) 12.Health faucet (upto Rs. 2200/-) 13. Waterproofing up to 4 feet height 14.Diverter (Rs. 6500/-) 15.Piller Cock (Rs.5500/-) including Labour. Make: Hinware/ jaquar/ Kohlar (french Gold Finish) or equivalent. Removing old and Providing new cPVC & PVC pipe lines Connection	0	3.00	1,16,000.00	3,48,000.00	Rates shall be equivalent or as per MRP
5.1.2	Bib cock (upto Rs. 4300/-) for washing machine	Nos	1.00	4,300.00	4,300.00	
5.1.3	LABOUR & MATERIAL (KITCHEN)	Nos	1.00	10,000.00	10,000.00	
	SINK & Dishwasher shall be added, Points for plumbing work					
6	Carpentry Work					
6.1	All Over Area					
6.1.1	P & F of sangwan team wood door frame, single and double rebeat (internal & External) as per requirements, finish in PU polish, including 3" wide wooden moulding	Sq.Ft.	7.00	14,000.00	98,000.00	

6.1.2	VANITY COUNTER TOP Providing Counter top Somany Full body tile (Up to Rs. 180/-)	Sq.Ft.	3.00	6,000.00	18,000.00	VANITY (WITH EXTRA Rs. 8000/ VANITY) (CAN BE ADDED IF REQ)Fixing Carcase & Shutters in commercial board (Make: century sainik) exterior & Internal finish shall be in laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettich equivalent) Soft Close; Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).1 Drawer and open self below
6.2	All Over Area					
6.2.1	INTERNAL DOORS	Sq.Ft.	7.00	14,500.00	1,01,500.00	

	Providing & Fixing of 19mm thick commercial board in BWP Board (Make: Durian) with Laminate (Make: Advance/ Greenlam) (Stopper (Up to Rs. 200/-), hinges (Upto Rs. 150/-) , Tower Bolt (Up to Rs. 200/-) Hardware to be installed in heavy duty SS (Grade 304). Lock (Make: Godrej)(Up to Rs 1500/-)					
6.3	Living Room					
6.3.1	TV Panel	Sq.Ft.	63.00	900.00	56,700.00	
	Providing & Fixing Carcase & Shutters in HDHMR (Make: Green/ century) exterior & Internal finish shall be in laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettich equivalent) Soft Close; Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).					
6.4	Dining Room					

6.4.1	BACK WALL PANELLING Providing & Fixing HDHMR (Make:Green or equivalent) finish in PU polish with required moulding and SS stripe.	0	93.28	1,025.00		can be added if required
6.5	Dining Room					
6.5.1	CROCKERY UNIT	Sq.Ft.	45.50	1,900.00	86,450.00	
	Providing & Fixing Carcase & Shutters in commercial board (Make: Century sainik) exterior & Internal laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).Profile Light (Up to 1 Year Warranty) included & Glass shutter with Profile.					
6.6	Entrance/Foyer					
6.6.1	SHOE RACK Providing & Fixing Carcase & Shutters in HDHMR (Make: Century/ Green) exterior & Internal finish shall be in (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).	Sq.Ft.	12.25	1,700.00	20,825.00	Profile Light (Up to 1 Year Warranty) excluded
6.7	Master Bedroom					

6.7.1	WARDROBE Providing & Fixing Carcase & Shutters in commercial board (Make: Century sainik) exterior & Internal laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).	Sq.Ft.	68.00	1,880.00	1,27,840.00	Profile Light (Up to 1 Year Warranty) excluded
6.8	Master Bedroom					
6.8.1	DRESSER Providing & Fixing Carcase & Shutters in HDHMR(Make: Green/ Century) exterior & Internal finish shall be (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent). Profile Light (Up to 1 Year Warranty), 5MM thick mirror (AIS, Saintgobain) included & Glass shutter with Profile.	Sq.Ft.	24.00	1,700.00	40,800.00	
6.9	Bedroom 1					

6.9.1	WARDROBE Providing & Fixing Carcase & Shutters in commercial board (Make: Century sainik) exterior & Internal laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).	0	56.00	1,880.00	1,05,280.00	Profile Light (Up to 1 Year Warranty) excluded
6.10	Bedroom 1					
6.10.1	DRESSER	Sq.Ft.	28.00	1,700.00	47,600.00	
	Providing & Fixing Carcase & Shutters in HDHMR (Make: Green/ Century) exterior & Internal finish shall be (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent). Profile Light (Up to 1 Year Warranty), 5MM thick mirror (AIS, Saintgobain) included & Glass shutter with Profile.					
6.11	Bedroom 1					

6.11.1	TV Panel Providing & Fixing Carcase & Shutters in HDHMR (Make: Green/ Century) exterior & Internal finish shall be in laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic equivalent) Soft Close; Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).	Sq.Ft.	68.00	900.00		can be added if required
6.12	Bedroom 2					
6.12.1	WARDROBE Providing & Fixing Carcase & Shutters in commercial board (Make: Century sainik) exterior & Internal finish shall be (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent). Profile Light (Up to 1 Year Warranty), 5MM thick mirror (AIS, Saintgobain) included & Glass shutter with Profile.	Sq.Ft.	68.00	1,880.00	1,27,840.00	Profile Light (Up to 1 Year Warranty) excluded
6.13						
6.13.1	DRESSER	Sq.Ft.	39.97	1,700.00	67,949.00	

	Providing & Fixing Carcase & Shutters in HDHMR (Make: Green/ Century) exterior & Internal finish shall be (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic or equivalent) Soft Close; Long Handles (Up To Rs. 1000/Pcs) & Short Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent). Profile Light (Up to 1 Year Warranty), 5MM thick mirror (AIS, Saintgobain) included & Glass shutter with Profile.					
6.14	Bedroom 2					
6.14.1	TV Panel	Sq.Ft.	50.00	900.00	45,000.00	
	Providing & Fixing Carcase & Shutters in HDHMR (Make: Green/ Century) exterior & Internal finish shall be in laminate (Make: Greenlam, Advance, Virgo or equivalent); Channels & Hinges (Make: Hettic equivalent) Soft Close; Handles (Up to Rs. 500/ Pcs.) Drawer locks (Make: Godrej/ Harrison or equivalent).					
6.15	KITCHEN					

S. No.	Particulars	Unit	Area	Rate	Amount	Remarks
6.15.1	MODULAR KITCHEN	Nos	1.00	3,00,000.00	3,00,000.00	
	Providing and Fixing of Carcas below Slab only & Shutter in (Make: Century sainik or equivalent) Counter shall be in Full Body Tile (Make: Somany Full body tile. Up to 180/sqft) Innotech Fitting (Make: Hettich equivalent) in drawers and basket, exterior finish in Laminate(Make: Skydecor/ Advance Acrylic or equivalent) Pantry unit (up to Rs. 10000/-) as per approved shade using of G Profile for handle as per approve shade. Channels & Hinges (Make: Hettich or equivalent) Soft Close.					
7	Plumbing Work					
7.1	Kitchen					
7.1.1	Jayna or equivalent Sink (SS 304) single bowl	Nos	1.00	8,500.00	8,500.00	Rates shall be equivalent or as per MRP
7.2	Kitchen					
7.2.1	Sink Mixture & RO point	Nos	1.00	5,000.00	5,000.00	
8	Fabricating Work					
8.1.1	Providing & fixing of MS jaal with vertical bars of 10x10mm thick at back side	Kg	620.00	125.00	77,500.00	Added as per discussion of the extension of balcony & Dining windows
9	Painting Work					
9.1	All Over Area					
9.1.1	PAINT WORK Providing and applying Royal Shyne Premium (Make:Asian) with applying coat of 2 Coat of Putty, coats of Water-Based acrylic primer, 2 coats of chalk mitty putty and 2 coat Paint with proper base and finishing. Providing Samples over wall before executing the final colour. Including wall paper on wall if required instead of paint	Sq.Ft.	4,290.00	55.00	2,35,950.00	will be calculated As per actual measurement
10	POP Punning					
10.1	All Over Area					
10.1.1	POP PUNNING WALL	Sq.Ft.	2,086.00	28.00	58,408.00	
	Providing PoP Punning (3MM layer)					

11	UPVC Work					
11.1	All Over Area					
11.1.1	UPVC SLIDING DOOR	Sq.Ft.	204.00	780.00	1,59,120.00	
	Providing and fixing UPVC Sliding Door (3 Track) 2 Sliders Shutters + 1 Mosquito Mesh, 6mm Thick Single glazed unit Toughened Glass (Make: Modi Guard, Saint Gobain) or Openable (Single)/ Fixed (Brand: Simta Astrix or equivalent)					
	Sub Total				₹ 29,04,930.28	
	Add Misc & Transportation (5%)				₹ 1,45,246.51	
	Grand Total Amount				₹ 30,50,176.79	
	Net Total Amount				₹ 30,50,176.79	

The item rates written above shall be based on the tentative area as per unit, the final measurement shall be applicable as per the actual site measurements at the time of final bill.

- All above rates are exclusive of GST will be charged separately as per applicable rates by govt.
- 5% Miscellaneous Cost & Transportation cost shall be applicable on final bill (already calculation in Estimate).
- All Measurements units like square feet/ Running Feet/ Counts/ Cubic Feet etc. shall be measurable for all items as per the common understanding/ fair practice in the market.
- For all such items where only Brand is mentioned without any price range such items shall be considered with staring range of the product within the same Brand or can be considered at prevailing market prices based on selection of client.
- All Extra required work shall not be included in payment schedule, if required that it can be added later with 90% advance and 10% after work is completed.
- The rates quoted in the schedule below shall be for complete work in all respects and shall include all direct, indirect and contingent costs, expenses including charges for scaffolding, centering material and shuttering, hiring for tools and machinery, and temporary sheds for storage of materials, labor removal of debris, etc.

9. The contractor works in all respects of civil and interior work as mentioned above within 120 days from the date of start of execution work (Excluding the time for demolition, if required). It is an express stipulation that time is the essence of the contract. Rs. 1,000/- day penalty shall be applicable over contractor in case of any delay. Work delayed due to late payment received from owner's end, natural disaster/ calamity/pandemic, strike or any other Govt. Notice affecting continuation of work shall be considered and contractor shall not be liable for the same. The contractor shall submit the work schedule within 100 days of this date and weekly site meetings will be held to monitor the progress, the same period shall be considered for mobilization on site.
10. Owner shall allow the accommodation of Labours, permission for work, Material, & Storage over the site for 24 x 7 around the clock. Owner shall provide storage for water (Approx. 1000 Ltr.)/ connection for water and electricity during the period of construction. All these charges shall be borne by the owner. Owner shall also be liable to pay fee/ rental/ Charges (authorized/ unauthorized)/ permission charges related to Govt. officials/ authority if any.
11. The contractor shall be liable for security of material/ Tools and any other miscellaneous items over site that is under contractor's scope. Owner shall not pay for any such theft, if it happens.
12. White goods like Electrical fixtures, Microwave, Fridge, Geyser, Hobbs, Chimney, Coffee Machine etc. are not included in the part of this agreement. Fitting of appliances shall be in the scope of contractor wherever required.
13. Contractor shall be liable for penalty of Rs 10,000/- each time, if found change in agreed material or company Brand over site without any information to Executing Agency.

14. PAYMENT SCHEDULE: -

a	Advance Rs. 3,00,000 + GST	- Before starting the project.
b	2 nd Stage payment Rs. 7,00,000 + GST	- After 90% Demolition work - After starting of door framework over site - After starting of False Ceiling Work (Material Procurement)
c	3 rd Stage payment Rs. 7,00,000 + GST	- After completion of 70% False Ceiling work - After completion of conduiting work & 90% wiring work - After completion of replacing of Plumbing Pipes in all toilets - After Starting of MS work (Material procurement) - After Starting of Tile Work in Toilets
d	4 th Stage Rs. 7,00,000 + GST	- After completion of 95% false ceiling - After 80% of tile flooring work - After Completion of 95% MS Work - After completion of 50% (wooden structure) kitchen work & wardrobe work in all bedrooms. - After starting of TV units in Living & Bedroom (Material procurement)
e	5 th Stage Rs. 4,00,000 + GST	- After completion of 80% kitchen work - After completion of 70% wardrobe in rooms - After Completion of 80% Door carpentry work - After starting of PoP punning work (Material procurement) - After completion of 95% tile work in toilets & Flooring
f	6 th Stage (Final Payment) + GST	- Within 15 days of final handover and snag list if any is requested to share within 3 days of Handover.

14. Bills shall be provided from the name of the execution firm i.e. M/S Arya Enterprises.
15. Final payment shall be payable at the latest by or within 15 days of the Final Site Handover of Interior Work. All measurement snag list or any discrepancies shall be shared by legal means in written format within 3 days of handover.

Payment Details:

Account Name : M/s Arya Enterprises
Account Number : 013663400003010
IFSC Code : YESB0000136
Branch : Cannaught Palace, New Delhi

16. Any extra work if required shall be payable at 90% in advance and 10% after completion of the work.
17. All the materials (as specified in the schedule), colors & shades shall be as per approval from client.
18. All quantities and quality check must be part of ongoing work, and must be checked time to time, Clarity on quantity must be conveyed from the side of both the parties, the same must be resolved within 03 days and conveyed thru any legal means within 03 days of handover of the project so that final payment shall not be held over these clarifications.
19. **AUTHORIZED VARIATIONS:**
All authorized variations for which a rate or price may not have been previously agreed upon shall be measured and valued by the Owner. Items, for which no such rate exist shall be worked at actual cost to the contractor at site of work plus 18% GST of the actual cost provided the architect duly certifies such cost.
20. **MATERIALS AND WORKMANSHIP:**
 - a) All materials and workmanship shall be the acceptable of the respective kind and described in the schedules.
 - b) The Owner shall have the power to order the removal from the works of any defective materials or work to order substitutions of materials of work in accordance with this agreement and the schedules.
21. The Owner while **retaining possession of the site** has only permitted the contractor to enter upon the property for the purposes of constructing a residential house. The owner shall be subsequently entitled at any time to freely enter upon and exercise all acts of possession and ownership over the aforesaid residential site.
22. The mobilization period shall be 3 to 5 days after the advance payment received from the client.
23. In case of any legal action taken by either of the parties the matter shall be resolved with the arbitrators/ Courts of Delhi only.

Hereby, both parties agree on the conditions, rates & proper work quality as per specifications as written in this agreement:

Mr. Noor
Owner Name

Mr. Prabhat Arya
for M/S Arya Enterprises

OWNER
DATE: 17.05.2026

CONTRACTOR

Witness:

1.

2.

